

Report on Design and Construction of Drilled Piers

Reported by ACI Committee 336

ACI 336.3R-14



American Concrete Institute
Always advancing



Report on Design and Construction of Drilled Piers

Copyright by the American Concrete Institute, Farmington Hills, MI. All rights reserved. This material may not be reproduced or copied, in whole or part, in any printed, mechanical, electronic, film, or other distribution and storage media, without the written consent of ACI.

The technical committees responsible for ACI committee reports and standards strive to avoid ambiguities, omissions, and errors in these documents. In spite of these efforts, the users of ACI documents occasionally find information or requirements that may be subject to more than one interpretation or may be incomplete or incorrect. Users who have suggestions for the improvement of ACI documents are requested to contact ACI via the errata website at <http://concrete.org/Publications/DocumentErrata.aspx>. Proper use of this document includes periodically checking for errata for the most up-to-date revisions.

ACI committee documents are intended for the use of individuals who are competent to evaluate the significance and limitations of its content and recommendations and who will accept responsibility for the application of the material it contains. Individuals who use this publication in any way assume all risk and accept total responsibility for the application and use of this information.

All information in this publication is provided "as is" without warranty of any kind, either express or implied, including but not limited to, the implied warranties of merchantability, fitness for a particular purpose or non-infringement.

ACI and its members disclaim liability for damages of any kind, including any special, indirect, incidental, or consequential damages, including without limitation, lost revenues or lost profits, which may result from the use of this publication.

It is the responsibility of the user of this document to establish health and safety practices appropriate to the specific circumstances involved with its use. ACI does not make any representations with regard to health and safety issues and the use of this document. The user must determine the applicability of all regulatory limitations before applying the document and must comply with all applicable laws and regulations, including but not limited to, United States Occupational Safety and Health Administration (OSHA) health and safety standards.

Participation by governmental representatives in the work of the American Concrete Institute and in the development of Institute standards does not constitute governmental endorsement of ACI or the standards that it develops.

Order information: ACI documents are available in print, by download, on CD-ROM, through electronic subscription, or reprint and may be obtained by contacting ACI.

Most ACI standards and committee reports are gathered together in the annually revised ACI Manual of Concrete Practice (MCP).

American Concrete Institute
3880 Country Club Drive
Farmington Hills, MI 48331
Phone: +1.248.848.3700
Fax: +1.248.848.3701

www.concrete.org

Report on Design and Construction of Drilled Piers

Reported by ACI Committee 336

William H. Oliver Jr., Chair

Bernard H. Hertlein, Secretary

Clyde N. Baker Jr.
William D. Brant
Diane M. Campione
Joseph P. Colaco
Conrad W. Felice

Rudolph P. Frizzi
Shraddhakar Harsh
Matthew Johnson
John W. Johnston
Johnny H. Kwok

Hugh S. Lacy
Adam C. Ramme
Satish K. Sachdev
Rodrigo Salgado
Harold R. Sandberg

Edward J. Ulrich

Consulting members
Ronald W. Harris
John F. Seidensticker

This report covers design and construction of 30 in. (760 mm) diameter or larger foundation piers constructed by excavation of a hole in a subgrade that is later filled with concrete. The 30 in. (760 mm) diameter boundary is an arbitrary size; smaller-diameter drilled piers can be designed and installed in accordance with ACI 543R. Although determination of overall pier size and concrete section design are two basic drilled pier design procedures, emphasis is focused on the determination of overall pier size, which is affected by the interaction between subgrade and pier. Because pier capacity is significantly affected by construction means and methods, the licensed design professional should understand these limitations. Construction methods described include excavation, casing, reinforcing steel installation, and concrete placement. Acceptance criteria and recommended procedures for construction, engineering, and evaluation are presented.

Keywords: bearing capacity; caisson; casing; excavation; foundation; geotechnical engineering; lateral pressure; lining; slurry; trench

CONTENTS

CHAPTER 1—INTRODUCTION AND SCOPE, p. 2

- 1.1—Introduction, p. 2
- 1.2—Scope, p. 2

CHAPTER 2—NOTATION AND DEFINITIONS, p. 2

- 2.1—Notation, p. 2
- 2.2—Definitions, p. 2

CHAPTER 3—GENERAL CONSIDERATIONS, p. 3

- 3.1—General, p. 3
- 3.2—The structural and geotechnical teams, p. 3
- 3.3—Factors to consider, p. 4
- 3.4—Pier types, p. 4
- 3.5—Geotechnical considerations, p. 5

CHAPTER 4—DESIGN, p. 7

- 4.1—Loads, p. 7
- 4.2—Loading conditions, p. 8
- 4.3—Vertically loaded piers, p. 9
- 4.4—Laterally loaded piers, p. 9
- 4.5—Piers socketed in rock, p. 15
- 4.6—Strength design of piers, p. 16
- 4.7—Pier configuration, p. 16

CHAPTER 5—CONSTRUCTION MEANS AND METHODS, p. 17

- 5.1—Excavation and casing, p. 17
- 5.2—Placing reinforcement, p. 18
- 5.3—Dewatering, concreting, and removal of casing, p. 18
- 5.4—Slurry displacement method, p. 19
- 5.5—Safety, p. 21

CHAPTER 6—CONSTRUCTION ENGINEERING AND TESTING, p. 22

- 6.1—Scope, p. 22
- 6.2—Geotechnical field representative, p. 22
- 6.3—Preconstruction activities, p. 22
- 6.4—Construction geotechnical engineering procedures, p. 23
- 6.5—Concrete placement, p. 25

ACI Committee Reports, Guides, and Commentaries are intended to provide guidance in planning, designing, executing, and inspecting construction. This document is intended for the use of individuals who are competent to evaluate the significance and limitations of its content and recommendations and who will accept responsibility for the application of the material it contains. The American Concrete Institute disclaims any and all responsibility for the stated principles. The Institute shall not be liable for any loss or damage arising therefrom.

Reference to this document shall not be made in contract documents. If items found in this document are desired by the Architect/Engineer to be a part of the contract documents, they shall be restated in mandatory language for incorporation by the Architect/Engineer.

ACI 336.3R-14 supersedes ACI 336.3R-93 and was adopted and published August 2014.

Copyright © 2014, American Concrete Institute.

All rights reserved including rights of reproduction and use in any form or by any means, including the making of copies by any photo process, or by electronic or mechanical device, printed, written, or oral, or recording for sound or visual reproduction or for use in any knowledge or retrieval system or device, unless permission in writing is obtained from the copyright proprietors.

- 6.6—Post-construction assessment, p. 27
- 6.7—Reports, p. 27
- 6.8—Criteria for acceptance, p. 27
- 6.9—Corrective measures, p. 28

CHAPTER 7—REFERENCES, p. 28

Authored documents, p. 28

CHAPTER 1—INTRODUCTION AND SCOPE

1.1—Introduction

This report addresses design and construction of drilled pier foundations constructed by digging, drilling, or otherwise excavating a hole in the subgrade that is subsequently filled with plain or reinforced concrete. Although structural design and construction of drilled pier foundations are the primary objectives of this report, relevant aspects of geotechnical engineering are also discussed, as variations in subgrade properties have a critical influence on design, construction, and subsequent performance. Successful drilled pier design, construction, and performance requires reliable data on the applied loads and supporting subgrade. Because construction limitations often govern design, combined cooperation among the geotechnical engineer, structural engineer, and drilled pier contractor are essential.

1.2—Scope

This report is generally limited to piers of 30 in. (760 mm) or larger diameter, made by open or slurry stabilized construction methods. A 30 in. (760 mm) diameter boundary is an arbitrary size. Although smaller-diameter drilled piers have been designed and installed in accordance with this report, it is difficult to detect sidewall collapse. Refer to ACI 308.3R-03 and ACI 543R for concrete piles having diameters smaller than 30 in. (760 mm), piles installed by the use of hollow stem caissons, or other pile types. Also beyond the scope of this report are rectangular columns on spread footings in open excavations and foundations constructed without excavations by methods such as mortar intrusion or mixed in place.

Piers installed by tapping or ramming concrete or aggregate into an excavated shaft are beyond the scope of this report. Engineers and contractors have used the terms “caissons,” “foundation piers,” “bored piers,” “drilled shafts,” and “drilled piers” interchangeably. The term “drilled pier” is used in this report. A drilled pier with an enlarged base can be called a belled caisson, belled pier, or drilled and under-reamed footing. Drilled pier foundations excavated and concreted with water or slurry in the hole have been called slurry shafts, piers installed by wet-hole methods, or piers installed by slurry displacement methods.

CHAPTER 2—NOTATION AND DEFINITIONS

2.1—Notation

- A_b = pier base area, in.² (mm²)
- A_p = pier shaft surface area, in.² (mm²)
- D = dead load, lb (N)

- D_g = dead loads from the supported structure and weight of the pier (gross weight of the pier), lb (N)
- d = diameter of pier, in. (mm)
- E = earthquake load, lb (N)
- E_c = modulus of elasticity, psi (MPa)
- F = vertical load, lb (N)
- FS = allowable strength design safety factor
- FS_1 = allowable strength design safety factor for bearing resistance
- FS_2 = allowable strength design safety factor for side resistance
- f_p = average side resistance, ton/ft² (kPa)
- f_z = unit load transfer from shaft to ground at depth z , ton/ft² (kPa)
- H_g = horizontal shear at ground surface, lb (N)
- I = moment of inertia, in.⁴ (mm⁴)
- k_s = modulus of horizontal soil bearing reaction, psi (MPa)
- L = live load, lb (N)
- M_g = moment at ground surface, usually applied to pier by superstructure, in.-lb (N-mm)
- N = number of blows in a standard penetration test
- P_{an} = anchorage resistance, lb (N)
- P_q = ultimate end bearing acting at the base, lb (N)
- P_{up} = uplift force, lb (N)
- p = subgrade resistance per unit length along the pier, lb/in. (N/mm)
- p - y = lateral load deflection curve at an element of pier, lb/in., in. (N/mm, mm)
- Q = ultimate axial capacity, tons (kN)
- q_b = unit end-bearing pressure, ton/ft² (kPa)
- S_n = force from side friction, lb (N)
- S_p = positive side resistance, lb (N)
- S_{p1} = positive side resistance, acting upward on the pier; normally caused by downward movement of the pier relative to surrounding soil, lb (N)
- T = relative stiffness factor
- W = wind load, lb (N)
- w_b = movement of the pier at depth z , in. (mm)
- w_z = unit deflection corresponding to f_z , in. (mm)
- y = lateral deflection of pier, in. (mm)

2.2—Definitions

ACI provides a comprehensive list of definitions through an online resource, “ACI Concrete Terminology,” <http://concrete.org/Tools/ConcreteTerminology.aspx>. Definitions provided here complement that source.

bearing-type pier—a pier that receives its principal vertical capacity from a subgrade layer at the bottom of the pier.

bell—an enlargement at the pier bottom to spread the load over a larger area, or to engage additional subgrade mass for uplift loading conditions; also called **under-ream**.

cap—an upper pier termination, usually placed separately, to correct deviations from desired location, facilitate anchor bolt or dowel setting within acceptable tolerances, or combine two or more piers into a unit supporting a column.

casings—a protective temporary or permanent steel tube, usually cylindrical in shape, lowered into the excavated hole