

IN-LB

Inch-Pound Units

SI

International System of Units

Guide for Precast Concrete Tunnel Segments

Reported by ACI Committee 533

ACI 533.5R-20



American Concrete Institute
Always advancing



Guide for Precast Concrete Tunnel Segments

Copyright by the American Concrete Institute, Farmington Hills, MI. All rights reserved. This material may not be reproduced or copied, in whole or part, in any printed, mechanical, electronic, film, or other distribution and storage media, without the written consent of ACI.

The technical committees responsible for ACI committee reports and standards strive to avoid ambiguities, omissions, and errors in these documents. In spite of these efforts, the users of ACI documents occasionally find information or requirements that may be subject to more than one interpretation or may be incomplete or incorrect. Users who have suggestions for the improvement of ACI documents are requested to contact ACI via the errata website at <http://concrete.org/Publications/DocumentErrata.aspx>. Proper use of this document includes periodically checking for errata for the most up-to-date revisions.

ACI committee documents are intended for the use of individuals who are competent to evaluate the significance and limitations of its content and recommendations and who will accept responsibility for the application of the material it contains. Individuals who use this publication in any way assume all risk and accept total responsibility for the application and use of this information.

All information in this publication is provided "as is" without warranty of any kind, either express or implied, including but not limited to, the implied warranties of merchantability, fitness for a particular purpose or non-infringement.

ACI and its members disclaim liability for damages of any kind, including any special, indirect, incidental, or consequential damages, including without limitation, lost revenues or lost profits, which may result from the use of this publication.

It is the responsibility of the user of this document to establish health and safety practices appropriate to the specific circumstances involved with its use. ACI does not make any representations with regard to health and safety issues and the use of this document. The user must determine the applicability of all regulatory limitations before applying the document and must comply with all applicable laws and regulations, including but not limited to, United States Occupational Safety and Health Administration (OSHA) health and safety standards.

Participation by governmental representatives in the work of the American Concrete Institute and in the development of Institute standards does not constitute governmental endorsement of ACI or the standards that it develops.

Order information: ACI documents are available in print, by download, through electronic subscription, or reprint and may be obtained by contacting ACI.

Most ACI standards and committee reports are gathered together in the annually revised the ACI Collection of Concrete Codes, Specifications, and Practices.

American Concrete Institute
38800 Country Club Drive
Farmington Hills, MI 48331
Phone: +1.248.848.3700
Fax: +1.248.848.3701

www.concrete.org

Guide for Precast Concrete Tunnel Segments

Reported by ACI Committee 533

David Wan, Chair

Mehdi Bakhshi*†
George F. Baty
Harry A. Chambers‡
George F. Baty

Benjamin Lavon
James Lewis
Donald F. Meinheit
Brian D. Miller

Verya Nasri†
Karen Polanco
Larbi M. Sennour
Venkatesh Seshappa

Michael H. Weber
Dennis R. Wittry
Wahid A. Zatar

*Chair of task group who prepared this report.

†Members who prepared this report.

‡Deceased.

Consulting Members

Aaron W. Fink
Sidney Freedman

Ava Shypula
Weilan Song

The worldwide trend in construction is toward mechanization and automation. This trend has led to continued rapid progress of mechanized tunneling. Advantages over conventional tunnel construction methods include, but are not limited to, occupational health and safety, faster advance rates, and reducing construction labor requirements. Mechanized tunneling in soft ground using tunnel boring machines is often associated with installing precast concrete segmental lining. However, very little industry-wide guidance has been provided by practice and code organizations. This document provides guidelines for precast concrete tunnel construction, including the most recent developments and practical experience, in addition to information on all aspects of design and construction. These guidelines are based on the knowledge and the experience gained on numerous precast tunnel projects in the United States, and available national and international guidelines often used as industry references.

Keywords: design; durability; fiber-reinforced joint; lining; precast; segment; tolerance; tunnel.

CONTENTS

CHAPTER 1—INTRODUCTION AND SCOPE, p. 2

1—Introduction, p. 2

1.2—Scope, p. 2

CHAPTER 2—NOTATION AND DEFINITIONS, p. 3

2.1—Notation, p. 3

2.2—Definitions, p. 5

CHAPTER 3—DESIGN PHILOSOPHY AND SEGMENTAL RING GEOMETRY, p. 6

3.1—Load and resistance factor design, p. 6

3.2—Governing load cases and load factors, p. 6

3.3—Design approach, p. 6

3.4—Segmental ring geometry and systems, p. 7

CHAPTER 4—DESIGN FOR PRODUCTION AND TRANSIENT STAGES, p. 12

CHAPTER 5—DESIGN FOR CONSTRUCTION STAGES, p. 14

5.1—Tunnel boring machine thrust jack forces, p. 15

5.2—Tail skin back grouting pressure, p. 19

5.3—Localized back grouting (secondary grouting) pressure, p. 20

5.4—TBM backup load, p. 20

ACI Committee Reports, Guides, and Commentaries are intended to provide guidance in planning, designing, executing, and inspecting construction. This document is intended for the use of individuals who are competent to evaluate the significance and limitations of its content and recommendations and who will accept responsibility for the application of the material it contains. The American Concrete Institute disclaims any and all responsibility for the stated principles. The Institute shall not be liable for any loss or damage arising therefrom.

Reference to this document shall not be made in contract documents. If items found in this document are desired by the Architect/Engineer to be a part of the contract documents, they shall be restated in mandatory language for incorporation by the Architect/Engineer.

ACI 533.5R-20 was adopted and published April 2020.

Copyright © 2020, American Concrete Institute.

All rights reserved including rights of reproduction and use in any form or by any means, including the making of copies by any photo process, or by electronic or mechanical device, printed, written, or oral, or recording for sound or visual reproduction or for use in any knowledge or retrieval system or device, unless permission in writing is obtained from the copyright proprietors.

CHAPTER 6—DESIGN FOR FINAL SERVICE STAGES, p. 21

- 6.1—Earth pressure, groundwater, and surcharge loads, p. 22
- 6.2—Longitudinal joint bursting load, p. 27
- 6.3—Loads induced due to additional distortion, p. 28
- 6.4—Other loads, p. 29

CHAPTER 7—DETAILED DESIGN CONSIDERATIONS, p. 32

- 7.1—Concrete strength and reinforcement, p. 32
- 7.2—Concrete cover, p. 34
- 7.3—Curing, p. 34
- 7.4—Reinforcement spacing, p. 34
- 7.5—Fiber reinforcement, p. 35

CHAPTER 8—TESTS AND PERFORMANCE EVALUATION, p. 37

CHAPTER 9—DESIGN FOR SERVICEABILITY LIMIT STATE, p. 38

- 9.1—Verification for SLS in tunnel segments, p. 38
- 9.2—Stress verification, p. 38
- 9.3—Deformation verification, p. 38
- 9.4—Cracking verification, p. 39

CHAPTER 10—DESIGN OF SEGMENT GASKET, p. 40

- 10.1—Gasket materials, p. 40
- 10.2—Water pressure and gasket design, p. 41
- 10.3—Gasket relaxation and factor of safety, p. 42
- 10.4—Tolerances and design for required gap/offset, p. 42
- 10.5—Gasket load-deflection, p. 44
- 10.6—Gasket groove design, p. 44
- 10.7—New development in gasket systems, p. 45

CHAPTER 11—CONNECTION DEVICES AND FASTENING SYSTEMS, p. 47

- 11.1—Bolts, dowels, and guiding rods, p. 47
- 11.2—Design of connection device for gasket pressure, p. 47
- 11.3—Latest developments in joint connection systems, p. 48
- 11.4—Fastening systems to segments, p. 48

CHAPTER 12—TOLERANCES, MEASUREMENT, AND DIMENSIONAL CONTROL, p. 51

- 12.1—Production tolerances, p. 51
- 12.2—Measurement and dimensional control, p. 52
- 12.3—Cast ring and dimensional control frequency, p. 56
- 12.4—Construction tolerances, p. 59

CHAPTER 13—REPAIR OF DEFECTS, p. 60

CHAPTER 14—DURABILITY, p. 60

- 14.1—Conventional degradation mechanisms in tunnel linings, p. 60

- 14.2—Stray current corrosion in segmental tunnel linings, p. 66

- 14.3—Mitigation methods for stray current corrosion, p. 67

- 14.4—Durability under coupling multi-degradation factors, p. 70

- 14.5—Prescriptive-based approaches, p. 73

CHAPTER 15—REFERENCES, p. 76

- Authored documents, p. 77

CHAPTER 1—INTRODUCTION AND SCOPE

1.1—Introduction

Precast concrete segments are installed to support the excavation behind the tunnel boring machine (TBM) in soft ground, weak rock, and fractured hard rock applications. As shown in Fig. 1.1, the TBM advances by reacting against the completed rings of precast concrete segments that typically provide both the initial and final ground support as part of a one-pass lining system. These segments are designed to resist the permanent loads from the ground and groundwater as well as the temporary loads from production, transportation, and construction. Currently, very little guidance is provided for tunnel designers and contractors by local or international authorities, and there is an acute need for a document that clearly highlight the practical design principles, advances in construction, and the research needs in this area. Tunnel segments are generally reinforced to resist the tensile and compressive stresses at the ultimate limit states (ULS) and the serviceability limit state (SLS). Special attention is paid in this document to common methods in ULS and SLS designs of these elements. In addition, detailed design considerations are presented, such as concrete strength and reinforcement. Gasket design as sealing elements against groundwater inflow, connection devices, and fastening systems are introduced, followed by segment tolerances, measurement, and dimensional control systems.

1.2—Scope

This document provides analysis, design, and construction guidelines exclusively for one-pass precast segmental lining that is installed almost instantaneously with excavation inside TBM shields only a few yards behind the TBM cutterhead. Linings that are installed long after passing of an open-mode TBM, cast-in-place concrete linings, and segments of other materials such as steel and cast-iron segments do not fall within the scope of this guideline. Two-pass lining systems, which are no longer popular in modern tunnels, are not specifically discussed but can still benefit from the guidelines. More information about the two-pass linings can be found in ITA WG2 guidelines. This guideline provides methods of design and construction for TBM tunneling in soft ground as well as weak and fractured hard rock tunneling. The guidelines and recommendations in this document can be applied to tunnels of different types, such as road, railway, and subway tunnels; headrace, water supply, and waste water tunnels; and service, gas pipeline, and