

ACI 533R-11

**Guide for Precast
Concrete Wall Panels**

Reported by ACI Committee 533



American Concrete Institute®



American Concrete Institute®
Advancing concrete knowledge

First Printing
March 2012

Guide for Precast Concrete Wall Panels

Copyright by the American Concrete Institute, Farmington Hills, MI. All rights reserved. This material may not be reproduced or copied, in whole or part, in any printed, mechanical, electronic, film, or other distribution and storage media, without the written consent of ACI.

The technical committees responsible for ACI committee reports and standards strive to avoid ambiguities, omissions, and errors in these documents. In spite of these efforts, the users of ACI documents occasionally find information or requirements that may be subject to more than one interpretation or may be incomplete or incorrect. Users who have suggestions for the improvement of ACI documents are requested to contact ACI via the errata website at www.concrete.org/committees/errata.asp. Proper use of this document includes periodically checking for errata for the most up-to-date revisions.

ACI committee documents are intended for the use of individuals who are competent to evaluate the significance and limitations of its content and recommendations and who will accept responsibility for the application of the material it contains. Individuals who use this publication in any way assume all risk and accept total responsibility for the application and use of this information.

All information in this publication is provided "as is" without warranty of any kind, either express or implied, including but not limited to, the implied warranties of merchantability, fitness for a particular purpose or non-infringement.

ACI and its members disclaim liability for damages of any kind, including any special, indirect, incidental, or consequential damages, including without limitation, lost revenues or lost profits, which may result from the use of this publication.

It is the responsibility of the user of this document to establish health and safety practices appropriate to the specific circumstances involved with its use. ACI does not make any representations with regard to health and safety issues and the use of this document. The user must determine the applicability of all regulatory limitations before applying the document and must comply with all applicable laws and regulations, including but not limited to, United States Occupational Safety and Health Administration (OSHA) health and safety standards.

Participation by governmental representatives in the work of the American Concrete Institute and in the development of Institute standards does not constitute governmental endorsement of ACI or the standards that it develops.

Order information: ACI documents are available in print, by download, on CD-ROM, through electronic subscription, or reprint and may be obtained by contacting ACI.

Most ACI standards and committee reports are gathered together in the annually revised ACI Manual of Concrete Practice (MCP).

American Concrete Institute
38800 Country Club Drive
Farmington Hills, MI 48331
U.S.A.
Phone: 248-848-3700
Fax: 248-848-3701

www.concrete.org

ISBN 978-0-87031-756-9

Guide for Precast Concrete Wall Panels

Reported by ACI Committee 533

Brian D. Miller, Chair

David Wan, Secretary

George F. Baty
Harry A. Chambers
Aaron W. Fink
Sidney Freedman
Harry A. Gleich
Allan R. Kenney
Benjamin Lavon

Donald F. Meinheit
Larbi M. Sennour
Venkatesh Seshappa
Ava Shyputa

Thomas J. Grisinger, Consulting Member
Weilan Song, Consulting Member

This guide presents recommendations for precast concrete wall panels. It should be used with ACI 318-08, "Building Code Requirements for Structural Reinforced Concrete," which is legally binding when adopted by the local authority. This guide discusses the basic principles of design, tolerances, materials, fabrication, installation, quality requirements, and testing.

Keywords: admixtures; aggregates; architectural concrete; coatings; cracking (fracturing); curing; deflection; design; drying shrinkage; fabrication; formwork; inspection; installation joints (junction); precast concrete panels; repairs; sandwich panels; sealants; structural design; surface defects; tolerances; volume change.

CONTENTS

Chapter 1—General considerations, p. 2

- 1.1—Introduction
- 1.2—Scope
- 1.3—Responsibility
- 1.4—Aesthetic considerations

Chapter 2—Notation and definitions, p. 4

- 2.1—Notation
- 2.2—Definitions

ACI Committee Reports, Guides, and Commentaries are intended for guidance in planning, designing, executing, and inspecting construction. This document is intended for the use of individuals who are competent to evaluate the significance and limitations of its content and recommendations and who will accept responsibility for the application of the material it contains. The American Concrete Institute disclaims any and all responsibility for the stated principles. The Institute shall not be liable for any loss or damage arising therefrom.

Reference to this document shall not be made in contract documents. If items found in this document are desired by the Architect/Engineer to be a part of the contract documents, they shall be restated in mandatory language for incorporation by the Architect/Engineer.

Chapter 3—Wall panel design, p. 4

- 3.1—Introduction
- 3.2—Design guidelines
- 3.3—Effective dimensions
- 3.4—Limiting dimensions
- 3.5—Serviceability
- 3.6—Connections
- 3.7—Architectural features

Chapter 4—Tolerances, p. 8

- 4.1—General
- 4.2—Reasons for tolerances
- 4.3—Role of the engineer/architect
- 4.4—Product tolerances for wall panels
- 4.5—Installation tolerances for wall panels
- 4.6—Interfacing considerations
- 4.7—Clearances and tolerances for constructibility

Chapter 5—Materials, p. 13

- 5.1—Introduction
- 5.2—Portland cement
- 5.3—Aggregates for structural or backup concrete
- 5.4—Facing aggregates
- 5.5—Admixtures
- 5.6—Insulating materials and wythe connectors for insulated sandwich walls
- 5.7—Reinforcement
- 5.8—Inserts and miscellaneous hardware
- 5.9—Curing materials and sealers
- 5.10—Joint sealants and fillers

ACI 533R-11 supersedes ACI 533R-93 and was adopted and published March 2012. Copyright © 2012, American Concrete Institute.

All rights reserved including rights of reproduction and use in any form or by any means, including the making of copies by any photo process, or by electronic or mechanical device, printed, written, or oral, or recording for sound or visual reproduction or for use in any knowledge or retrieval system or device, unless permission in writing is obtained from the copyright proprietors.

- 5.11—Chemical retarders
- 5.12—Form release agents

Chapter 6—Panel fabrication and delivery, p. 19

- 6.1—General requirements
- 6.2—Molds (forms and casting beds)
- 6.3—Concrete proportioning and mixing
- 6.4—Reinforcement and wythe connectors
- 6.5—Concrete placement
- 6.6—Surface finishes
- 6.7—Concrete curing
- 6.8—Storage
- 6.9—Delivery

Chapter 7—Installation, p. 31

- 7.1—Planning and preparation
- 7.2—Unloading and handling
- 7.3—Job site storage
- 7.4—Installation
- 7.5—Tolerances
- 7.6—Cleaning
- 7.7—Patching and repairing

Chapter 8—Quality requirements and tests, p. 41

- 8.1—Introduction
- 8.2—Unacceptable defects
- 8.3—Structural adequacy
- 8.4—Prestressing
- 8.5—Materials
- 8.6—Testing fresh concrete
- 8.7—Testing hardened concrete
- 8.8—Documentation

Chapter 9—References, p. 45

CHAPTER 1—GENERAL CONSIDERATIONS

1.1—Introduction

The widespread popularity of concrete as a building material can be attributed to the availability, favorable properties, and geographic distribution of its naturally-occurring mineral constituents. Concrete is easily formed and molded, comparatively economical, and durable in its finished state. Architectural precast panel use has increased because of the nature of concrete as a material and the fact that prefabricated components add to construction efficiency. By exposing decorative aggregates, using veneer facing materials, and by varying sizes, shapes, and textures of panels, the engineer/architect can respond creatively to client needs.

1.2—Scope

This document provides guidelines for specifying, planning, designing, fabrication, and erecting precast concrete wall panels. Although the focus is on precast wall panels produced in established precasting plants, site precasting is an option that has been used successfully. Tilt-up concrete, as discussed in ACI 551.1R-05, is a variation of site precasting. ACI 533R should aid in establishing and maintaining quality

site fabrication as well as plant fabrication of precast wall panels.

This guide covers non-load-bearing or load-bearing panels, fabricated of normal or lightweight concrete. Panels may be one of the following types:

- Solid
- Insulated (sandwich)
- Ribbed
- Hollow-core
- Sculptured

In addition to reinforced panels, lightly prestressed (effective prestress, after all losses, between 150 and 225 psi [1.0 and 1.7 MPa]) and prestressed panels are covered. Structural design considerations addressed in Chapter 3 include the use of panels as shear wall components.

Emphasis is placed on wall panels with a minimal exposed aggregate concrete surface finish. Smooth wall panels and panels with a textured or shaped architectural surface finish are included. Panels having natural stone veneer or ceramic veneer finishes are not covered in detail.

1.3—Responsibility

1.3.1 General—Contractual agreements should assign responsibilities to avoid disagreements on basic definitions and decisions originating from the specifying agency. A special report of an ad hoc committee for the responsibility for design of precast concrete structures was published by the Precast/Prestressed Concrete Institute (PCI 1988) and recommends assignment of authority and responsibility for design and construction of precast concrete structures.

This guide covers the design of panels by an engineer/architect. ACI Committee 533 presents supplemental design guidelines that are special to precast concrete wall panels and should be used with ACI 318-08. ACI 318-08 provides minimum design requirements and is legally binding when adopted by the local authority.

Overlapping responsibilities for the structural design of wall panels may introduce conflicts between the engineer/architect and general contractor regarding contract document review, design for handling, installation stresses, in-place loads, and adequacy of connections. It is essential that work assignments and responsibilities be clearly defined in the contractual arrangements.

1.3.2 Structural design—The engineer/architect can benefit from preconstruction contact with panel producers. Handling and installation procedures vary widely, and guidelines for these operations should correspond with local practices but be consistent with Chapter 3 of this guide. Most precasters maintain an engineering staff to prepare contract documents and the engineer/architect should interact with this group to obtain constructive advice and suggestions concerning local practice, fabrication details, and fabrication capabilities. When possible, this discussion should take place during the initial design phases of a construction project. Once a job is released for bidding and the structural concepts have been established, changes may be difficult to implement.