

# Recommended Practice for Steel Pipeline Construction Quality Management Systems

API RECOMMENDED PRACTICE 1177  
FIRST EDITION, NOVEMBER 2017



AMERICAN PETROLEUM INSTITUTE

## Special Notes

API publications necessarily address problems of a general nature. With respect to particular circumstances, local, state, and federal laws and regulations should be reviewed.

Neither API nor any of API's employees, subcontractors, consultants, committees, or other assignees make any warranty or representation, either express or implied, with respect to the accuracy, completeness, or usefulness of the information contained herein, or assume any liability or responsibility for any use, or the results of such use, of any information or process disclosed in this publication. Neither API nor any of API's employees, subcontractors, consultants, or other assignees, represent that use of this publication would not infringe upon privately owned rights.

Classified areas may vary depending on the location, conditions, equipment, and substances involved in any given situation. Users of this specification should consult with the appropriate authorities having jurisdiction.

Users of this specification should not rely exclusively on the information contained in this specification. Sound business, scientific, engineering, and safety judgment should be used in employing the information contained herein. API is not undertaking to meet the duties of employers, service providers, or suppliers to warn and properly train and equip their employees, and others exposed, concerning health and safety risks and precautions, nor undertaking their obligations to comply with authorities having jurisdiction.

Information concerning safety and health risks and proper precautions with respect to particular materials and conditions should be obtained from the employer, the service provider or supplier of that material, or the material safety datasheet.

API publications may be used by anyone desiring to do so. Every effort has been made by the Institute to assure the accuracy and reliability of the data contained in them; however, the Institute makes no representation, warranty, or guarantee in connection with this publication and hereby expressly disclaims any liability or responsibility for loss or damage resulting from its use or for the violation of any authorities having jurisdiction with which this publication may conflict.

API publications are published to facilitate the broad availability of proven, sound engineering and operating practices. These publications are not intended to obviate the need for applying sound engineering judgment regarding when and where these publications should be used. The formulation and publication of API publications is not intended in any way to inhibit anyone from using any other practices.

All rights reserved. No part of this work may be reproduced, translated, stored in a retrieval system, or transmitted by any means, electronic, mechanical, photocopying, recording, or otherwise, without prior written permission from the publisher. Contact the Publisher, API Publishing Services, 1220 L Street, NW, Washington, DC 20005.

## Foreword

Nothing contained in any API publication is to be construed as granting any right, by implication or otherwise, for the manufacture, sale, or use of any method, apparatus, or product covered by letters patent. Neither should anything contained in the publication be construed as insuring anyone against liability for infringement of letters patent.

**Shall:** As used in a standard, “shall” denotes a minimum requirement in order to conform to the specification.

**Should:** As used in a standard, “should” denotes a recommendation or that which is advised but not required in order to conform to the specification.

**May:** As used in a standard, “may” denotes a course of action permissible within the limits of a standard.

**Can:** As used in a standard, “can” denotes a statement of possibility or capability.

This specification was produced under API standardization procedures that ensure appropriate notification and participation in the developmental process and is designated as an API standard. Questions concerning the interpretation of the content of this publication or comments and questions concerning the procedures under which this publication was developed should be directed in writing to the Director of Standards, American Petroleum Institute, 1220 L Street, NW, Washington, DC 20005. Requests for permission to reproduce or translate all or any part of the material published herein should be addressed to the director.

Generally, API standards are reviewed and revised, reaffirmed, or withdrawn at least every five years. A one-time extension of up to two years may be added to this review cycle. Status of the publication can be ascertained from the API Standards Department, telephone (202) 682-8000. A catalog of API publications and materials is published annually by API, 1220 L Street, NW, Washington, DC 20005.

This standard shall become effective on the date printed on the cover but may be used voluntarily from the date of distribution.

Suggested revisions are invited and should be submitted to the Standards Department, API, 1220 L Street, NW, Washington, DC 20005, [standards@api.org](mailto:standards@api.org).

# Contents

	Page
<b>1 Scope</b> .....	<b>1</b>
<b>2 Normative References</b> .....	<b>1</b>
<b>3 Definitions and Abbreviations</b> .....	<b>1</b>
<b>3.1 Terms and Definitions</b> .....	<b>1</b>
<b>3.2 Abbreviations</b> .....	<b>4</b>
<b>4 Quality Management System Requirements</b> .....	<b>6</b>
<b>4.1 General</b> .....	<b>6</b>
<b>4.2 Management Responsibility</b> .....	<b>7</b>
<b>4.3 Organization Capability</b> .....	<b>8</b>
<b>4.4 Documentation Requirements</b> .....	<b>9</b>
<b>4.5 Control of Records</b> .....	<b>10</b>
<b>4.6 Change Management</b> .....	<b>10</b>
<b>4.7 Risk Assessment and Management</b> .....	<b>10</b>
<b>5 Pipeline Construction</b> .....	<b>11</b>
<b>5.1 Planning</b> .....	<b>11</b>
<b>5.2 Legal and Organizational Requirements</b> .....	<b>12</b>
<b>5.3 Verification of Engineering and Design</b> .....	<b>12</b>
<b>5.4 Contract Development and Review</b> .....	<b>13</b>
<b>5.5 Procurement of Materials and Equipment</b> .....	<b>14</b>
<b>5.6 Pipeline Construction</b> .....	<b>15</b>
<b>5.7 Inspection</b> .....	<b>45</b>
<b>5.8 Control of Nonconformances</b> .....	<b>45</b>
<b>6 QMS Measurement, Analysis, and Improvement</b> .....	<b>46</b>
<b>6.1 General</b> .....	<b>46</b>
<b>6.2 Monitoring, Measuring, and Metrics</b> .....	<b>46</b>
<b>6.3 Analysis of Data</b> .....	<b>47</b>
<b>6.4 Improvement</b> .....	<b>47</b>
<b>6.5 Audits</b> .....	<b>48</b>
<b>6.6 Management Review</b> .....	<b>48</b>
<b>Annex A (informative) Construction Quality Management Systems</b>	<b>50</b>
<b>Annex B (informative) Personnel Training, Qualification, and Competence</b>	<b>54</b>
<b>Bibliography</b> .....	<b>56</b>
<b>Figures</b>	
<b>A.1 QMS Framework Scope</b> .....	<b>52</b>
<b>A.2 Quality Management Documents</b> .....	<b>53</b>
<b>A.3 QMS and Project Reviews</b> .....	<b>53</b>

## Background

This document is a framework for a quality management system (QMS) for onshore pipeline construction. While this document may be used for facility and station construction, that is not the focus of the document. The QMS developed for onshore pipeline projects shall include and document the following, which are discussed in more detail throughout this recommended practice:

- defined project quality objectives and personnel accountability;
- processes to establish and maintain the appropriate project organizational structure;
- processes to establish and maintain the appropriate training and qualification of internal and contracted personnel;
- processes to facilitate and verify quality throughout project design, contracting, procurement, manufacturing, fabrication, and construction;
- processes to prevent, detect, mitigate, and eliminate potential and actual nonconformance with project procedures, specifications, and referenced standards, or noncompliance with regulations, as well as verification and documentation of actions taken and the outcome;
- assessment of the achievement of quality objectives throughout the construction project; and
- methods to measure each process's effectiveness and enact continuous improvement of the QMS.

This framework can be used to develop a stand-alone QMS or to integrate quality management into an organization's existing corporate management system. In this document, "organization" is defined as the entity using this document to develop its own QMS for pipeline construction.

The organization may be the owner company, operating company, engineering and/or construction contractor, supplier, or other stakeholder in pipeline construction that has its own QMS. Typically, the owner/operating company will utilize contractors and suppliers on a pipeline construction project, which have their own QMS in alignment with this document. When the QMS is developed, the term "organization" should be replaced with the responsible entities, such as operating company, owner-company, contractor, or supplier. Elements of this RP can be met in aggregate by the organizations constructing the pipeline.

Additionally, some processes covered in this framework may already be implemented by an organization; for example, change management. Existing processes may be modified to address the quality concerns identified in this framework.

To be applicable to the wide range of organizations within the pipeline industry, the RP was developed to be flexible and scalable. The RP was developed for use by organizations of varying size and scope. While the QMS elements will apply to each organization, the application of these elements are to be appropriate for the size of the organization, the scope of the project, and the risk to the public and environment.

Each pipeline construction project is unique. While typical pipeline construction activities are included in this document, they may not be all-inclusive. Other construction activities may be relevant and should be addressed on a project-by-project basis, utilizing the principles of this RP. Likewise, it is recognized that the identified construction activities may not be applicable to every pipeline construction project. It is the organization's responsibility to consider unique quality issues applicable to their projects and address them accordingly through their organization-specific QMS.

Much of the input to this document is based on information provided in the PHMSA/DNV GL OAPUS314MJRU (PP087506), Rev. 3, report, *Improving Quality Management Systems (QMS) for Pipeline Construction Activities*, dated September 2, 2015.

The management system principles are applied in a recurring manner to achieve continuous improvement. The Plan–Do–Check–Act (PDCA) cycle is a four-step model for carrying out these efforts (Figure 1).

This cycle can be applied to the management system as a whole, to individual construction projects, and to individual elements and processes within the system. Continuous improvement is at the core of many management systems, and its principal aim is to encourage creating strategies and plans, executing those strategies and plans in line with guidelines, evaluating those actions for conformity, and using those results to adjust the next generation of plans. This cycle is iterative.

The components of the PDCA cycle are:

**Plan:** This step entails establishing the objectives and processes necessary to deliver results in accordance with the organization's policies and the expected goals. By establishing output expectations and completeness and accuracy of the process is also a part of the targeted improvement.

**Do:** This step is the execution of the plan designed in the previous step.

**Check:** This step entails the review of the results compared with established objectives. Those results are compared to the expected goals to ascertain any differences and deviations in implementation from the plan.

**Act:** This step is where the organization takes actions to improve process performance. This may include corrective actions focusing on significant differences between actual and planned results.

Continuous improvement occurs when the PDCA cycle is repeated.




Figure 1—Continuous Improvement Cycle (PDCA)

Additional background information on QMS is contained in Annex A, Construction Quality Management Systems.

Currently in preview, click buy full version

# Recommended Practice for Steel Pipeline Construction Quality Management Systems

## 1 Scope

This recommended practice establishes minimum Quality Management System (QMS) processes for organizations that own, operate, construct, or provide construction-related services for onshore carbon and low-alloy steel pipelines used in the transportation of hazardous liquids, carbon dioxide, and gas. This recommended practice specifies the elements of a QMS to manage the construction process systematically from design verification, materials manufacturing, procurement, construction, inspection, and testing to initiation of operations.

## 2 Normative References

The following referenced documents are indispensable for the application of this document. For dated references, only the edition cited applies. For undated references, the edition that is incorporated by reference in the code of federal regulations of the referenced document applies (including any addenda/errata).

API Standard 1104, *Welding of Pipelines and Related Facilities*

## 3 Definitions and Abbreviations

### 3.1 Terms and Definitions

For the purposes of this document, the following terms and definitions apply.

#### 3.1.1

##### **acceptance criteria**

Specified limits of acceptability applied to process, service, or product characteristics.

#### 3.1.2

##### **activity quality plan**

##### **AQP**

Document(s) that establishes procedures, minimum personnel qualifications, roles and responsibilities, inspection methods, and record requirements of construction activities. The intent of an AQP is to identify quality concerns and methods of control.

NOTE For pipeline construction, an activity quality plan is developed for each construction task (stringing, welding, backfilling, etc.).

#### 3.1.3

##### **as-built surveying**

Process of collecting and documenting all of the pipeline attributes and their associated location and installation conditions along a pipeline.

#### 3.1.4

##### **backfilling**

Replacement of the native soil in the trench surrounding the installed pipeline. Padding may be used in addition to backfilling.