

AS 2896:2021



STANDARDS
Australia



Medical gas systems — Installation and testing of non-flammable medical gas pipeline systems

currently in review, click buy full version

AS 2896:2021

This Australian Standard ® was prepared by HE-017, Medical Gas Systems. It was approved on behalf of the Council of Standards Australia on 01 March 2021.

This Standard was published on 12 March 2021.

The following are represented on Committee HE-017:

- Australia New Zealand Industrial Gas Association
- Australian & New Zealand College of Anaesthetists
- Australian Industry Group
- Australian Society of Anaesthetists
- Engineers Australia
- Institute of Healthcare Engineering Australia
- Master Plumbers Australia and New Zealand
- NSW Health
- SA Health
- Therapeutic Goods Administration

This Standard was issued in draft form for comment as DR AS 2896:2020.

Keeping Standards up-to-date

Ensure you have the latest versions of our publications and keep up-to-date about Amendments, Rulings, Withdrawals, and new projects by visiting:

www.standards.org.au

ISBN 978 1 76113 241 4

Medical gas systems — Installation and testing of non-flammable medical gas pipeline systems

Originally as part of AS CZ9—1963.
Revised and redesignated as AS 2896—1986.
Previous edition 2011.
First edition 2021.

© Standards Australia Limited 2021

All rights are reserved. No part of this work may be reproduced or copied in any form or by any means, electronic or mechanical, including photocopying, without the written permission of the publisher, unless otherwise permitted under the Copyright Act 1968 (Cth).

Preface

This Standard was prepared by the Standards Australia Committee HE-017, Medical Gas Systems, to supersede AS 2896—2011.

The objective of this Standard is to set out requirements for the safety aspects, construction, testing and certification, operation and maintenance of non-flammable medical gas pipeline systems (MGPS) used for patient care, operating surgical tools, and therapeutic and diagnostic purposes. Non-flammable medical gas pipeline systems include medical suction pipeline systems.

Some of the major changes in this Standard include:

- (a) Distinguishing Levels 1 and 2 installations, based on the complexity of the health care facility and required MGPS.
- (b) Addition of [Appendix K](#) — Roles and responsibilities, to assist healthcare facilities in determining the commissioning process for medical gas pipeline systems.
- (c) Addition of [Appendix M](#) — Commissioning plan for Levels 1 and 2 installations.
- (d) Use of non-medical gases in reticulated systems and requirements for the detection and prevention of leaks and cross connection have been considered.
- (e) Addition of a requirement to ensure that any change-over alarm signals cannot be cancelled without first replacing empty cylinders on auto change-over manifolds.
- (f) Revision of the pressure and flow performance requirement and testing.
- (g) Introduction of requirements for the testing of purity for medical and surgical tool air.
- (h) Back-up for special care locations.
- (i) Additional requirements for gas scavenging.

A high quality of workmanship and experience is essential in the installation of medical gas pipelines. For medical gases not listed in [Clause 1.2](#), special pipeline designs may be required which are not covered by this Standard. For certain situations, e.g. hyperbaric conditions, special design and performance criteria for pipelines may be required.

Requirements in this Standard may be used as a guide for piping systems for other non-flammable medical gases and anaesthetic gas scavenging systems, but variations in the requirements may be necessary.

The inclusion of roles and responsibilities in AS 2896:2021 was approved by the Standards Development Committee on 2 November 2017, as a one-off exemption to the directives of Standardization Guide 009: Preparation of Standards for Legislative Adoption.

The terms “normative” and “informative” have been used in this Standard to define the application of the Appendix to which they apply. A “normative” Appendix is an integral part of a Standard, whereas an “informative” Appendix is only for information and guidance.

Contents

Preface	ii
Introduction	vii
Section 1 Scope and general	1
1.1 Scope	1
1.2 Application	1
1.3 Normative references	2
1.4 Terms and definitions	5
Section 2 Source of supply	9
2.1 General	9
2.2 Source of supply	9
2.3 Provision in case of failure of supply	9
2.3.1 Special care locations	9
2.3.2 Service facility inlets	9
2.4 Cylinder supply systems	10
2.4.1 General	10
2.4.2 Manifold	10
2.4.3 Manifold isolation	11
2.4.4 Manifold reset	11
2.4.5 Manifold headers	11
2.4.6 Manifold control panel	13
2.4.7 Cylinder racks	13
2.4.8 Marking of maximum working inlet pressure on the manifold	13
2.4.9 Cylinder lead	13
2.4.10 Liquefied gases in cylinders	13
2.4.11 Manifold alarm system	14
2.5 Pressure regulators	14
2.6 Design of gas control systems	14
2.7 Pressure relief valves	14
2.7.1 Primary pressure relief valve	14
2.7.2 Line pressure relief valve	15
2.7.3 Exhausts	15
2.8 Cryogenic systems	15
2.8.1 General	15
2.8.2 Secondary supply	15
2.8.3 Emergency supply	16
2.8.4 Primary main check valve	16
2.8.5 Cryogenic liquid vessel connections	16
2.9 Medical air systems	16
2.9.1 General	16
2.9.2 Medical air compressor-only source of supply	17
2.9.3 Medical air cylinder supply system	20
2.9.4 Non-therapeutic use of medical air	20
2.10 Medical suction systems	21
2.10.1 General	21
2.10.2 Pipeline suction system	21
2.10.3 Compressed gas venturi ejector-operated suction system	23
2.10.4 Anaesthetic gas scavenging systems	24
2.11 Surgical tool air systems	24
2.11.1 General	24
2.11.2 Air purity and dryness	25
2.12 Locations of source of gas supply	25
2.12.1 Security	25
2.12.2 Cryogenic liquid systems	25
2.12.3 Gas manifold system	26

2.12.4	Electrical fittings.....	26
2.12.5	Ambient temperature.....	26
2.13	Enclosures for cylinder supply systems.....	26
2.13.1	Cylinder storage.....	26
2.13.2	Interior and exterior enclosures.....	26
2.13.3	Specific requirements of interior enclosures.....	27
2.13.4	Specific requirements of exterior enclosures.....	27
2.13.5	Signs.....	27
2.13.6	Delivery access and docks.....	28
Section 3	General requirements.....	29
3.1	Locations.....	29
3.1.1	Anaesthetizing locations.....	29
3.2	Alarm systems.....	29
3.2.1	General.....	29
3.2.2	Installation requirements.....	31
3.2.3	Indicator panels.....	32
3.2.4	Operating alarm systems.....	33
3.3	Materials.....	34
3.3.1	General.....	34
3.3.2	Oxygen compatibility of components.....	34
3.3.3	Cleaning of pipelines and components.....	34
3.4	Requirements for pipelines.....	35
3.4.1	General.....	35
3.4.2	Pipeline design pressure and flows.....	35
3.4.3	In-line fittings and valves.....	36
3.4.4	Surgical tool air control panel.....	36
3.5	Pipeline isolation valves.....	36
3.5.1	General.....	36
3.5.2	Labelling.....	37
3.5.3	Valve boxes.....	37
3.5.4	Positioning.....	37
3.6	Terminal units and connectors.....	38
3.6.1	General.....	38
3.6.2	Form and dimensions.....	38
3.6.3	Secondary isolation valve.....	39
3.6.4	Pressure and flow requirements.....	39
3.6.5	Siting of terminal units.....	40
3.6.6	Identification.....	41
3.6.7	Discharge requirements for venturi ejector-operated suction terminal units.....	42
3.6.8	Connections between terminal units and equipment.....	42
3.6.9	Training / simulation areas.....	42
3.6.10	Auxiliary supply connectors.....	42
3.7	Identification of pipelines.....	42
3.7.1	General.....	42
3.7.2	Durability of identification.....	43
3.8	Examples of identification bands or labels for medical gas pipelines.....	43
Section 4	Installation requirements for pipelines.....	46
4.1	General.....	46
4.2	Electrical segregation.....	46
4.3	Protection of pipelines.....	46
4.3.1	General.....	46
4.3.2	In hazardous areas.....	46
4.3.3	Covered, buried or concealed pipelines.....	46
4.3.4	Electrical earth protection.....	48
4.4	Medical gas risers.....	48
4.5	Risers and droppers to terminal units.....	48
4.6	Sleeves.....	48

4.7	Contact with corrosive and other materials.....	48
4.8	Routing.....	48
4.9	Method of cutting into a MGPS.....	48
4.10	Interconnection.....	49
4.11	Pipeline supports.....	49
4.12	Copper pipeline joints.....	49
	4.12.1 Brazing.....	49
	4.12.2 Threaded and flange joints.....	49
	4.12.3 Brazing alloy.....	50
4.13	Connection to and modification of existing systems.....	50
	4.13.1 General.....	50
	4.13.2 Installation of an additional pipeline.....	50
	4.13.3 Sealing and labelling of isolation valve.....	51
	4.13.4 Marking of affected terminal units.....	51
	4.13.5 Testing for leaks after addition to the system.....	51
	4.13.6 Further testing.....	51
4.14	Services modules.....	51
	4.14.1 General.....	51
	4.14.2 Common requirements of all services modules.....	51
	4.14.3 Specific requirements of articulated services modules.....	53
	4.14.4 Specific requirements of columns and pedestals.....	53
	4.14.5 Specific requirements of wall mounted fixed services modules.....	54
Section 5	Testing, commissioning and certification.....	55
5.1	General.....	55
5.2	Testing, verification and certification.....	55
	5.2.1 Calibration and accuracy of instruments.....	56
5.3	Labelling of terminal units.....	56
5.4	Tests and checks on pipeline before concealment.....	56
	5.4.1 General.....	56
	5.4.2 Visual check.....	56
	5.4.3 Initial pressure test.....	57
	5.4.4 Test for medical air purity supplied from a compressor.....	57
	5.4.5 Test for surgical air purity supplied from a compressor.....	57
	5.4.6 Test for zone isolation valve shut-off and correct zoning.....	58
	5.4.7 Particulate matter tests.....	58
	5.4.8 Test for cross connections.....	58
5.5	Tests of the complete pipeline system.....	59
	5.5.1 General.....	59
	5.5.2 Total system pressure test.....	59
	5.5.3 Tests for flow rate and pressure.....	59
5.6	Filling system with the working gas and final commissioning.....	64
	5.6.1 General.....	64
	5.6.2 Filling with the working gas.....	64
	5.6.3 Test of source of supply system.....	65
	5.6.4 Checks on operation of alarm systems.....	65
	5.6.5 Test for gas identity.....	65
5.7	Certification of systems.....	68
5.8	As-installed drawings.....	68
	5.8.1 General.....	68
	5.8.2 Marking.....	68
	5.8.3 Updating.....	69
	5.8.4 Supplementary master drawing.....	69
	5.8.5 Emergency reference.....	69
Section 6	Maintenance.....	70
6.1	General.....	70
6.2	Safety and warning devices.....	70
6.3	Source of supply.....	70

6.3.1	Verification of correct operation.....	70
6.3.2	Inspection of manifold system.....	70
6.3.3	Checking of manifolds.....	71
6.3.4	Inspection of air compressors and suction pump system.....	71
6.4	Purity of medical air.....	72
6.4.1	General.....	72
6.4.2	Medical air.....	72
6.4.3	Surgical tool air.....	73
6.5	Maintenance of terminal units.....	73
6.6	Pressure gauges and pressure switches.....	73
6.7	Service manuals.....	74
6.8	Low pressure flexible hose assemblies and NIST fittings.....	74
6.9	Area zone isolation valve boxes and line isolation valves.....	74
Appendix A (informative) Guide to performance of typical medical gas pipeline systems.....		75
Appendix B (normative) Alarm systems.....		82
Appendix C (informative) Recommendations for materials and jointing techniques for the pipeline.....		86
Appendix D (informative) Outline for determining competence of installer.....		88
Appendix E (informative) Guidance to quality of workmanship in construction.....		89
Appendix F (normative) Fluxless brazing technique.....		90
Appendix G (informative) Logistic diagrams, test certificates, non-conformance report, contract completion certificate and terminal unit test form for testing of MGPS.....		97
Appendix H (informative) Relationship between temperature and certain pressure ranges of a given mass of perfect gas assuming volume of container is constant.....		110
Appendix I (informative) Test pressure/temperature variation for suction.....		111
Appendix J (informative) Conversion factors for units used in the measurement of pressure.....		112
Appendix K (normative) Roles and responsibilities.....		114
Appendix L (normative) Source of supply schematics.....		118
Appendix M (normative) Commissioning plans for new installations and modifications to existing installations.....		131
Bibliography.....		134

Introduction

Medical gas pipeline systems (MGPS) have some characteristic hazards, usually related to their original construction, modification, or repair rather than to problems arising during their working life. Medical gas pipelines are a life support system and as such require careful consideration of their design, construction and installation. Hazards include plumbing errors, use of materials incompatible with the gases to be delivered, obstruction of flow by material left in the pipelines, gas contamination by residual debris or accumulated foreign matter such as scale and organic contamination, and gas contamination due to chemical interaction between the gases and the pipeline components or foreign matter and condensation in pipelines. A particularly hazardous situation may occur when any amount of a hydrocarbon, such as oil, grease or other combustible compounds, comes in contact with oxidising gases such as oxygen or nitrous oxide.

For this reason, this Standard contains requirements that procedures be taken to avoid gas pipeline hazards, such as —

- (a) provision of documentation of tests and results from those responsible for the construction to the healthcare facility and retained as part of the facility's permanent records; and
- (b) independent inspection of the system by the healthcare facility using its own qualified personnel, or an experienced agent, who may be an independent outside contractor, to confirm and document the system's satisfactory operation.

The risks associated with the characteristic hazards as outlined above are increased where medical gases, apart from oxygen, medical air, surgical tool air or suction are reticulated in the healthcare facility or any MGPS where there are special care locations. For this reason the Standard has introduced the distinction between Level 1 and Level 2 work, on which further information can be found in [Appendix K](#). Levels 1 and 2 responsibilities checklists are detailed in [Table K.1](#) and [Table K.2](#) respectively.

Components of the medical gas system should be obtained and installed under the supervision of a person familiar with proper practices for its construction, installation and use. In order to establish competence of the personnel, the healthcare facility manager or operator should closely examine the previous experience of any contractor or installer proposing to work on or build a pipeline system. The healthcare facility manager or operator should also determine if the contractor or installer is familiar with the contents of this Standard which should be specified in the construction agreement. Unless otherwise specified, changes to the Standard do not act retrospectively.

All companies involved in the design, installation, testing, commissioning, and maintenance of medical gas systems should have suitable quality management systems, e.g. AS/NZS ISO 9001.

The maintenance and servicing of the gas pipeline system is the responsibility of the healthcare facility but may be delegated.

NOTES

Currently in preview, click buy full version

Australian Standard[®]

Medical gas systems — Installation and testing of non-flammable medical gas pipeline systems

Section 1 Scope and general

1.1 Scope

This Standard sets out requirements for the safety aspects, construction, testing and certification, operation and maintenance of non-flammable medical gas pipeline systems (MGPS) used for patient care, operating surgical tools, and therapeutic and diagnostic purposes. Non-flammable medical gas pipeline systems include suction pipeline systems used for human patient care.

The supply of oxygen from pressure swing absorption, oxygen concentrators and similar techniques is not covered in this Standard. The supply of synthetic air from proportioning units is not covered in this Standard.

The Standard does not apply to suction systems for laboratories and dental suction.

Some requirements are provided for the source of supply for the pipeline system as well as requirements for the pipeline system itself, terminal units and related warning systems.

The Standard also contains requirements for operating room services modules at which terminal units for medical gases are situated.

NOTE Patient care encompasses both medical and dental applications.

1.2 Application

This Standard applies to medical gases and suction services used in a MGPS.

The Standard applies to systems providing any of the following —

- (a) Oxygen;
- (b) Nitrous oxide;
- (c) Medical air;
- (d) Surgical tool air;
- (e) Carbon dioxide in oxygen ($\text{CO}_2 \leq 7\%$);
- (f) Nitrous oxide/oxygen 50/50;
- (g) Helium/oxygen mixtures ($\text{O}_2 \geq 20\%$);
- (h) Helium/oxygen mixtures ($\text{O}_2 < 20\%$);
- (i) Helium;
- (j) Carbon dioxide;
- (k) Medical suction;

NOTE In this Standard, “suction” is the preferred term, and corresponds with the internationally known term “vacuum”.

- (l) Scavenging.