

ASCE STANDARD

ASCE/EWRI

69-19

Standard Guidelines for Managed Aquifer Recharge

Currently in preview, click buy full version



ENVIRONMENTAL &
WATER RESOURCES
INSTITUTE

ASCE STANDARD

ASCE/EWRI

69-19

Standard Guidelines for Managed Aquifer Recharge



PUBLISHED BY THE AMERICAN SOCIETY OF CIVIL ENGINEERS

Library of Congress Cataloging-in-Publication Data

Names: American Society of Civil Engineers, author.

Title: Standard guidelines for managed aquifer recharge, ASCE/EWRI 69-19 / American Society of Civil Engineers.

Description: Reston, Virginia : American Society of Civil Engineers, [2020] | Includes bibliographical references and index. | Summary: "Ongoing demand for water supplies and the need for water storage have led to Managed Aquifer Recharge (MAR) becoming an increasingly important component for both storage and supply in regional water planning and management. In recent decades, MAR projects have been successfully implemented around the world"— Provided by publisher.

Identifiers: LCCN 2020006154 | ISBN 9780784415283 (paperback) | ISBN 9780784482179 (adobe pdf)

Subjects: LCSH: Artificial groundwater recharge—Standards—United States.

Classification: LCC TD404 .A48 2020 | DDC 627/.56021873—dc23

LC record available at <https://lccn.loc.gov/2020006154>

Published by American Society of Civil Engineers

1801 Alexander Bell Drive

Reston, Virginia 20191

www.asce.org/pubs

This standard was developed by a consensus standards development process that has been accredited by the American National Standards Institute (ANSI). Accreditation by ANSI, a voluntary accreditation body representing public and private sector standards development organizations in the United States and abroad, signifies that the standards development process used by ASCE has met the ANSI requirements for openness, balance, consensus, and due process.

While ASCE's process is designed to promote standards that reflect a fair and reasoned consensus among all interested participants, while preserving the public health, safety, and welfare that is paramount to its mission, it has not made an independent assessment of and does not warrant the accuracy, completeness, suitability, or utility of any information, apparatus, product, or process discussed herein. ASCE does not intend, nor should anyone interpret, ASCE's standards to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this standard.

ASCE has no authority to enforce compliance with its standards and does not undertake to certify products for compliance or to render any professional services to any person or entity.

ASCE disclaims and shall have no liability for any personal injury, property damage, financial loss, or other damages of any nature whatsoever, including without limitation any direct, indirect, special, exemplary, or consequential damages, resulting from any person's use of, or reliance on, this standard. Any individual who relies on this standard assumes full responsibility for such use.

ASCE and American Society of Civil Engineers—Registered in U.S. Patent and Trademark Office.

Photocopies and permissions. Permission to photocopy or reproduce material from ASCE publications can be requested by sending an e-mail to permissions@asce.org or by locating a title in ASCE's Civil Engineering Database (<http://cedb.asce.org>) or ASCE Library (<http://ascelibrary.org>) and using the "Permissions" link.

Errata: Errata, if any, can be found at <https://doi.org/10.1061/9780784415283>.

Copyright © 2020 by the American Society of Civil Engineers.

All Rights Reserved.

ISBN 978-0-7844-1528-3 (paper)

ISBN 978-0-7844-8217-9 (PDF)

Manufactured in the United States of America.

25 24 23 22 21 20 1 2 3 4 5

ASCE STANDARDS

In 2016, the Board of Direction approved revisions to the ASCE Rules for Standards Committees to govern the writing and maintenance of standards developed by ASCE. All such standards are developed by a consensus standards process managed by the ASCE Codes and Standards Committee (CSC). The consensus process includes balloting by a balanced standards committee and reviewing during a public comment period. All standards are updated or reaffirmed by the same process at intervals between five to ten years. Requests for formal interpretations shall be processed in accordance with Section 7 of ASCE Rules for Standards Committees, which are available at http://www.asce.org/uploadedFiles/Technical_Areas/Codes_and_Standards/Content_Pieces/asce-rules-standards-committees.pdf. Errata, addenda, supplements, and interpretations, if any, for this standard can also be found at <http://ascelibrary.org/>.

The provisions of this document are written in permissive language and, as such, offer to the user a series of options or instructions, but do not prescribe a specific course of action. Significant judgment is left to the user of this document.

This standard has been prepared in accordance with recognized engineering principles and should not be used without the user's competent knowledge for a given application. The publication of this standard by ASCE is not intended to warrant that the information contained therein is suitable for any general or specific use, and ASCE takes no position respecting the validity of patent rights. The user is advised that the determination of patent rights or risk of infringement is entirely his or her own responsibility.

A complete list of currently available standards is available in the ASCE Library (<https://ascelibrary.org/page/books/s-standards>).

This page intentionally left blank

Currently in preview, click buy full version

CONTENTS

PREFACE	ix
ACKNOWLEDGMENTS	xi
1 INTRODUCTION	1
1.1 Purpose	1
1.2 Scope	1
1.3 Organization of This Standard Guidelines	1
2 GROUNDWATER FUNDAMENTALS AND OCCURRENCE	3
2.1 Hydrologic Cycle	3
2.2 Groundwater Occurrence and Use	3
2.3 Groundwater Movement	3
2.3.1 Groundwater Recharge	4
2.3.2 Groundwater Storage	4
2.3.3 Groundwater Discharge	5
2.4 Groundwater Quality	5
3 MANAGED AQUIFER RECHARGE CONCEPTS	7
3.1 Purposes and Objectives	7
3.2 Components of a MAR System	7
3.3 Sources of Recharge Water	7
3.4 Pretreatment	7
3.5 Recharge	8
3.5.1 Surface Infiltration	9
3.5.2 Vadose (Unsaturated) Zone Recharge	12
3.5.3 Saturated Zone Recharge	12
3.6 Subsurface Storage	14
3.7 Recovery	14
3.8 Post-Treatment	14
3.9 End Uses	15
4 PLANNING	17
4.1 Initial Project Scoping	18
4.1.1 Define MAR Objectives	18
4.1.2 Preliminary Conceptual Plan	18
4.2 Initial Planning Activities	18
4.2.1 Develop Evaluation Criteria	19
4.2.2 Example Water Sources and Demand Criteria	19
4.2.3 Example Site Hydrogeology Criteria	20
4.2.4 Example Environmental Criteria	22
4.2.5 Example Implementation Criteria	23
4.2.6 Example Regulatory Criteria	24
4.2.7 Data Gathering for Criteria Evaluation	26
4.3 Detailed Planning: Identify Final Potential MAR Project Sites	26
4.3.1 Initial Project Site Screening	26
4.3.2 Detailed Evaluation	27
4.3.3 Selection of Sites for Feasibility Studies	29
4.3.4 Public Participation	29
4.3.5 Documentation	29

5	DESIGN AND TESTING	31
5.1	Design Phases	32
5.1.1	Conceptual Design	32
5.1.2	Preliminary Design	32
5.1.3	Final Design	32
5.1.4	Computer Modeling for Design	32
5.2	Design Considerations for Surface Facilities	33
5.2.1	Hydrogeology	33
5.2.2	Site Location, Size, Layout, and Operational Flexibility	33
5.2.3	Basin Design	34
5.2.4	Source Water	34
5.2.5	Water Quality	34
5.2.6	Pre- and Post-Treatment in Sedimentation Basins	34
5.2.7	Flow Structures	35
5.2.8	Flow Measurement	35
5.2.9	Maintenance	35
5.2.10	Mound Management	35
5.2.11	Groundwater Monitoring	36
5.2.12	Regulatory and Water Rights	36
5.3	Design Considerations for Subsurface Facilities	36
5.3.1	Hydrogeology	37
5.3.2	Well Field Layout	37
5.3.3	Well Design	38
5.3.4	Source Water	40
5.3.5	Water Quality and Compatibility	40
5.3.6	Water Treatment	40
5.3.7	Well Pumps and Piping	41
5.3.8	Corrosion Protection	42
5.3.9	Flow Measurement	42
5.3.10	Maintenance	43
5.3.11	Mound Management	43
5.3.12	Groundwater Monitoring	44
5.3.13	Regulatory and Water Rights	45
5.4	Pilot Testing	45
5.5	Design Documents	46
5.5.1	Preparation of Detailed Plans and Specifications	46
5.5.2	MAR Project Operation and Maintenance Plan	47
5.5.3	Periodic Review Schedule	47
5.5.4	Project Life	47
6	CONSTRUCTION	49
6.1	Site Preparation	50
6.2	Aquifer Construction for Surface Facilities	50
6.2.1	Site Excavation and Grading	50
6.2.2	Flow Structures and Piping	50
6.2.3	Facility Start-Up and Testing	51
6.3	Aquifer Construction for Subsurface Facilities	51
6.3.1	Drilling	51
6.3.2	Well Construction and Development	51
6.3.3	Aquifer and Well Performance Testing	52
6.3.4	Installation of Pump and Piping	52
6.3.5	Facility Start-Up and Testing	53
6.4	Electrical and SCADA System	53
6.5	Water Treatment Facilities	53
6.5.1	Common Water Treatment Issues	54
6.5.2	Facility Start-Up and Testing	54
6.6	Monitoring Equipment	54
6.7	Construction Records	54

7	OPERATIONS AND MAINTENANCE OF MAR FACILITIES	57
7.1	Start-Up and Training	58
7.1.1	Start-Up for Surface Recharge Facilities	58
7.1.2	Start-Up for Subsurface Recharge Facilities.	58
7.1.3	Operator Training	58
7.2	Operations and Maintenance for Surface Facilities	59
7.2.1	Operational Data and Analyses to Evaluate System Performance	60
7.2.2	Issues Affecting Surface MAR Operations	60
7.2.3	Clogging	61
7.2.4	Shallow Groundwater Levels	62
7.2.5	Undesirable Health Effects.	63
7.2.6	Facility Integrity	63
7.2.7	Site Security	63
7.3	Operations and Maintenance for Subsurface Facilities	63
7.3.1	Operational Data and Analyses to Evaluate System Performance	63
7.3.2	Issues Affecting Subsurface MAR Operations	64
7.3.3	Clogging of Recharge Wells.	64
7.3.4	Clogging of a Vadose Zone Well	66
7.3.5	Redevelopment of Recharge Wells	66
7.3.6	Sand Production	67
7.3.7	Site Security	68
7.3.8	Well Shutdown.	68
7.4	Water Quality Monitoring and Treatment	68
7.4.1	Monitoring	68
7.4.2	Treatment.	69
8	FACILITY CLOSURE.	71
8.1	Surface Infiltration Facilities	71
8.2	Subsurface Facilities	71
9	DATA COLLECTION AND ANALYSIS.	73
9.1	Data Collection.	73
9.2	Data Collection Phases.	73
9.2.1	Planning Phase.	73
9.2.2	Design Phase.	75
9.2.3	Construction Phase.	75
9.2.4	Operations and Maintenance Phase	75
9.2.5	Closure Phase	75
9.3	Data Organization and Management.	75
9.4	Data Needs for MAR Feasibility Studies	75
9.4.1	Source Water	76
9.4.2	Recharge Method	76
9.4.3	Aquifer Storage Recovery	77
9.4.4	Impact	80
9.5	Data Analysis.	81
9.5.1	Source Water Delivery Analysis.	81
9.5.2	Estimating Recharge and Recovery Volumes and Efficiency.	82
9.6	Modeling	85
9.6.1	Mass Balance Models	85
9.6.2	Numerical Models	85
9.6.3	Data Collection for Modeling	85
9.6.4	Determining Sensitive Variables.	86
9.6.5	Data Collection for Uncertainty Analysis	86
9.6.6	Geochemical Modeling	86
9.7	Monitoring and Compliance Data	87
9.8	Operational Data Collection	87
9.9	Data Collection to Evaluate Performance	87
9.10	Reporting	87

APPENDIXES 89
Appendix A. Glossary of Groundwater Terms 89
Appendix B. Notations and Symbols 95
Appendix C. MAR Regulations in the United States 97
Appendix D. Case Studies 103

REFERENCES 121

INDEX. 127

Currently in preview, click buy full versi

PREFACE

Ongoing demand for water supplies and the need for water storage have led to managed aquifer recharge (MAR) becoming an increasingly important component for both storage and supply in regional water planning and management. In recent decades, MAR projects have been successfully implemented around the world. However, many water resources professionals remain unaware of the benefits, techniques, standard practices, and applications of MAR. Over the past several decades much has been learned regarding how to design and implement a successful, cost-efficient MAR project and what pitfalls exist that prevent MAR success. Although there are extensive resources about various specialized aspects of MAR in the scientific literature, the US water resources sector has lacked an up-to-date, comprehensive document describing the state of the practice for MAR projects.

In 2001, the American Society of Civil Engineers' Environmental and Water Resources Institute (ASCE/EWRI) published the first standard guidelines on aquifer recharge as EWRI/ASCE 34-01,

Standard Guidelines for Artificial Recharge of Ground Water. As more MAR projects were developed and constructed, it became evident that the original standard needed to be modernized and upgraded to provide additional details on the planning, design, construction, and operation of MAR projects. In 2005, the ASCE/EWRI formed the Guideline Development Subcommittee for MAR. The purpose of this subcommittee was to provide a thorough and up-to-date document that describes the state of the practice for MAR projects. Beginning with the withdrawn standard (EWRI/ASCE 34-01), the subcommittee restructured the document to include details on planning, design, construction, operation, and monitoring of MAR projects, along with background information on groundwater and MAR concepts. This standard has been designed to meet the needs of water resources planners and stakeholders during the initial evaluation and planning phases, and the needs of engineers, hydrologists, and other professionals for standardization of MAR practices from conceptualization to operation.

This page intentionally left blank

ACKNOWLEDGMENTS

The ASCE and its Environmental and Water Resources Institute (EWRI) gratefully acknowledge the devoted efforts of the Managed Aquifer Recharge Guideline Development Subcommittee of the Managed Aquifer Recharge (MAR) Standards Committee of the Standards Development Council of EWRI. This standard was prepared by the MAR Standards Committee through ASCE's consensus standardization process in compliance with the ASCE Rules for Standards Committees and the procedures of ASCE's Codes and Standards Committee. ASCE's standardization process is accredited by the American National Standards Institute (ANSI).

The Managed Aquifer Recharge Guideline Development Subcommittee comprises individuals from many backgrounds, including consulting engineering, education, and government. Those individuals who served on the Managed Aquifer Recharge Guideline Development Subcommittee and actively participated in the drafting of ASCE Standard 69-19 are

Gordon McCurry, *Corresponding Editor and Co-Chair*

Peter Barkmann, *Co-Chair*

Doug Bartlett

Adam Hutchinson

Dennis McGrane

Stephanie Moore

Zhuping Sheng

Phyllis Stanin

Other current or former members of the Managed Aquifer Recharge Guideline Development Subcommittee who participated in review and balloting of the draft document include

Courtney Brand

Peter Dillon

Devin Galloway

Conrad Keyes, Jr.

Keith Prince

R. David G. Pyne

Ben Willardson

Greg Woodside

This page intentionally left blank

CHAPTER 1 INTRODUCTION

The growing demand for water supplies has led to an increasing need to store water to help meet periods of high demand. Aquifers form natural reservoirs that in many locations are capable of storing tremendous volumes of water. Worldwide, aquifers are being used more frequently for water storage for many reasons, including their proximity to sources of supply or demand, fewer environmental impacts relative to surface reservoirs, low evaporative losses and relatively low capital costs compared with surface storage in reservoirs, and their ability to be developed incrementally as needs arise. Storing water in aquifers can be as simple as enhancing natural recharge processes, or it can entail constructing a complex of recharge facilities.

Actively storing water in aquifers often involves the combined or conjunctive use of surface water and groundwater supplies, wherein water is recharged underground during times of surplus surface water for later withdrawal during times of surface water shortage. Implementation requires comprehensive planning, design, construction, ongoing monitoring, and active management to make best use of the combined surface water and groundwater resources. Because the recharge and storage of water in aquifers can be accomplished by a variety of intentional processes, it is referred to in this standard guidelines and elsewhere as managed aquifer recharge, or MAR. Some use the term ASR (aquifer storage and recovery) to denote the concepts referred to herein as MAR; these terms can be used interchangeably, although the authors of this standard guidelines prefer the term MAR.

1.1 PURPOSE

The purpose of this document is to provide a set of standard guidelines describing the activities required to implement a MAR project. This standard supersedes but builds upon *Standard Guidelines for Artificial Recharge of Ground Water* (ASCE 2001).

MAR projects are inherently interdisciplinary in their design, construction, implementation, and maintenance. This standard has been developed so that project personnel interested in, but perhaps with limited expertise with MAR, should benefit from understanding how to plan, design, construct, operate and maintain, and close MAR facilities based on the work of others.

1.2 SCOPE

MAR projects progress through a series of phases that normally begin with initial planning activities and then continue with design, construction, operation, and finally closure of recharge

facilities. This standard follows the progression through these phases, describing the key activities involved in each phase, and includes the economic, environmental, and legal (water rights, laws, and regulations) considerations, and site evaluation and field-testing procedures. Figure 1-1 illustrates the five primary phases of MAR project progression described in this standard. Greater detail of the activities is provided in subsequent sections. As shown by the arrows on Figure 1-1, at many stages of a MAR project, the process may step back to earlier phases as new data are obtained or conditions change.

MAR may be accomplished either by applying water to the ground surface, or shallow subsurface, for infiltration into the underlying aquifers or by injecting it directly into aquifers through wells. MAR projects can be regional in scale, targeting entire aquifer systems or local projects addressing the needs of individual wells or water supply systems. This standard has been developed to cover situations that may occur with many different types of MAR projects in many different types of hydrogeologic settings. This standard also applies to any project regardless of size.

1.3 ORGANIZATION OF THIS STANDARD GUIDELINES

Following the presentation of background material, this standard follows the progression of MAR activities outlined in Figure 1-1. The document begins with an introduction and overview in this chapter. Chapters 2 and 3 provide basic descriptions of groundwater and the key MAR concepts; these chapters are intended for readers with limited training and experience in MAR. MAR implementation begins with planning and evaluation, described in Chapter 4. Chapter 5 presents facility design. Chapters 6 through 8 present construction, operations, and closure, respectively.

Data collection is an essential component of each phase of a MAR project (Figure 1-1), and the level of effort varies during each phase, depending on specific project goals. Chapter 9 presents data collection methods and special considerations.

A glossary of key terms is found in Appendix A. Appendix B defines notations and symbols used in the standard. Appendix C lists MAR regulations in the United States. Case studies that provide examples of MAR projects are summarized in Appendix D. The dimensions and quantities used in this document are in International System of Units (SI units) followed by conversion to US Customary units in parentheses per the ASCE Rules for Standards Committees (2016).