



**Illuminating**  
ENGINEERING SOCIETY

**LIGHTING PRACTICE:  
THE COMMISSIONING PROCESS APPLIED TO  
LIGHTING AND CONTROL SYSTEMS  
AN AMERICAN NATIONAL STANDARD**

Currently in preview, click buy full version



**ANSI/IES LP-8-20**

**LIGHTING PRACTICE:  
THE COMMISSIONING PROCESS  
APPLIED TO LIGHTING AND  
CONTROL SYSTEMS  
AN AMERICAN NATIONAL STANDARD**

Publication of this report  
has been approved by IES.  
Suggestions for revisions  
should be directed to IES.

**Prepared by  
The IES Lighting Commissioning Committee**



*Copyright 2020 by the Illuminating Engineering Society.*

*Approved by the IES Standards Committee January 6, 2020 as a Transaction of the Illuminating Engineering Society.*

*Approved March 13, 2020 as an American National Standard.*

*All rights reserved.* No part of this publication may be reproduced in any form, in any electronic retrieval system or otherwise, without prior written permission of the IES.

Published by the Illuminating Engineering Society, 120 Wall Street, New York, New York 10005

IES Standards and Guides are developed through committee consensus and produced by the IES Office in New York. Careful attention is given to style and accuracy. If any errors are noted in this document, they should be forwarded to Brian Liebel, Director Standards, at [standards@ies.org](mailto:standards@ies.org) or the above address for verification and correction. The IES welcomes and urges feedback and comments.

Printed in the United States of America.

ISBN# 978-0-87995-267-9

---

## DISCLAIMER

IES publications are developed through the consensus standards development process approved by the American National Standards Institute. This process brings together volunteers representing varied viewpoints and interests to achieve consensus on lighting recommendations. While the IES administers the process and establishes policies and procedures to promote fairness in the development of consensus, it makes no guaranty or warranty as to the accuracy or completeness of any information published herein.

The IES disclaims liability for any injury to persons or property or other damages of any nature whatsoever, whether special, indirect, consequential or compensatory, directly or indirectly resulting from the publication, use of, or reliance on this document.

In issuing and making this document available, the IES is not undertaking to render professional or other services for or on behalf of any person or entity. Nor is the IES undertaking to perform any duty owed by any person or entity to someone else. Anyone using this document should rely on his or her own independent judgment or, as appropriate, seek the advice of a competent professional in determining the exercise of reasonable care in any given circumstances.

The IES has no power, nor does it undertake, to police or enforce compliance with the contents of this document. Nor does the IES list, certify, test or inspect products, designs, or installations for compliance with this document. Any certification or statement of compliance with the requirements of this document shall not be attributable to the IES and is solely the responsibility of the certifier or maker of the statement.

## AMERICAN NATIONAL STANDARD

Approval of an American National Standard requires verification by ANSI that the requirements for due process, consensus, and other criteria have been met by the standards developer.

Consensus is established when, in the judgment of the ANSI Board of Standards Review, substantial agreement has been reached by directly and materially affected interests. Substantial agreement means much more than a simple majority, but not necessarily unanimity. Consensus requires that all views and objections be considered, and that a concerted effort be made toward their resolution.

The use of American National Standards is completely voluntary; their existence does not in any respect preclude anyone, whether that person has approved the standards or not, from manufacturing, marketing, purchasing, or using products, processes, or procedures not conforming to the standards.

The American National Standards Institute does not develop standards and will in no circumstances give an interpretation to any American National Standard. Moreover, no person shall have the right or authority to issue an interpretation of an American National Standard in the name of the American National Standards Institute. Requests for interpretations should be addressed to the secretariat or sponsor whose name appears on the title page of this standard.

CAUTION NOTICE: This American National Standard may be revised at any time. The procedures of the American National Standards Institute require that action be taken to reaffirm, revise, or withdraw this standard no later than five years from the date of approval. Purchasers of American National Standards may receive current information on all standards by calling or writing the American National Standards Institute.

**Prepared by the IES Lighting Commissioning Committee**

**Michael Myer, *Chair***

**Members**

J. J. Deringer	Y. H. Hiebert	M. W. Mehl
W. T. Grandzik	K. Lapalme	S. Segal
M. K. Hefter	T. L. Larsen	D. M. Welch

**Advisory Members**

D. G. Salinas	X. Varghese
---------------	-------------

---

**Acknowledgments**

Special thanks for Jill Klores, LC, Essential Light Design Studio and Ardra Zinkon, MIES, IALD Associate, Tec Inc. for their contributions to this document.

Special thanks to Craig DiLouie, ZING Communications, Inc. for his writing and editing contributions to this document.

Special thanks to the Lighting Controls Association and Seattle City Light for contributing detailed Construction Checklists and Performance Testing procedures for popular lighting control systems.

Special thanks to Peerless Lighting, Énergie Lighting, Litecontrol Corp., a-light and Tivoli, LLC for contributing to the Design Checklists and WattStopper for contributing to the occupancy sensor Construction Checklist.

# CONTENTS

<b>1.0</b>	<b>Introduction and Scope</b> .....	<b>1</b>
<b>1.1</b>	<b>Introduction</b> .....	<b>1</b>
1.1.1	Benefits .....	1
1.1.2	Commissioning and Lighting Design .....	1
<b>1.2</b>	<b>Scope</b> .....	<b>4</b>
<b>2.0</b>	<b>Definitions (Adapted from ASHRAE Guideline 0-2005)</b> .....	<b>4</b>
<b>3.0</b>	<b>Pre-design Phase</b> .....	<b>6</b>
<b>3.1</b>	<b>The Commissioning Team</b> .....	<b>6</b>
<b>3.2</b>	<b>The Commissioning Plan</b> .....	<b>6</b>
<b>3.3</b>	<b>Owner's Project Requirements (OPR)</b> .....	<b>7</b>
<b>3.4</b>	<b>Other Pre-design Phase Activities</b> .....	<b>10</b>
<b>4.0</b>	<b>Design Phase</b> .....	<b>13</b>
<b>4.1</b>	<b>Basis of Design</b> .....	<b>13</b>
<b>4.2</b>	<b>Project Phasing</b> .....	<b>13</b>
<b>4.3</b>	<b>Design Criteria</b> .....	<b>18</b>
<b>4.4</b>	<b>Other Design Phase Activities</b> .....	<b>19</b>
<b>5.0</b>	<b>Construction Phase</b> .....	<b>20</b>
<b>5.1</b>	<b>Construction Administration and Occupancy</b> .....	<b>20</b>
<b>5.2</b>	<b>Performance Testing</b> .....	<b>21</b>
<b>5.3</b>	<b>Issues Log</b> .....	<b>22</b>
<b>5.4</b>	<b>Systems Manual</b> .....	<b>22</b>
<b>6.0</b>	<b>Occupancy and Operations Phase</b> .....	<b>23</b>
<b>6.1</b>	<b>Long-term Commissioning</b> .....	<b>23</b>
	<b>Annex A – Example Basis of Design (BOD) Document</b> .....	<b>24</b>
	<b>Annex B – The Role of Design Criteria in the Commissioning Process</b> .....	<b>24</b>
	<b>Annex C – Construction Checklists for Lighting and Control Systems</b> .....	<b>29</b>
	<b>Annex D – Sample Performance Testing Procedures for Daylighting and Lighting Control Systems</b> .....	<b>37</b>
	<b>References</b> .....	<b>42</b>

## 1.0 Introduction and Scope

### 1.1 Introduction

The lighting design intent should be monitored throughout the entire construction process, particularly in the final installation. The correct luminaires, lamps, ballasts, drivers, and controls should be properly installed and perform according to criteria that achieve user acceptance and satisfy the owner's operational needs.

*Commissioning* describes a process undertaken to achieve this goal for buildings and their systems, including lighting. It is a quality assurance process used to verify that buildings and their installed systems satisfy owner and designer performance criteria initially and throughout the life of the building.

To be more specific, the term *commissioning* in this document is defined as the Commissioning Process for buildings and systems as described within *Guideline 0-2005, The Commissioning Process*, published by the American Society of Heating, Refrigerating and Air-Conditioning Engineers (ASHRAE).<sup>1</sup> The guideline was also published by the National Institute of Building Sciences (NIBS) as *Guideline 0, The Total Building Commissioning Process*.

This overall building Commissioning Process is illustrated in **Figure 1-1**. As shown, commissioning occurs throughout the delivery of the project. It begins at project inception (during the pre-design phase), proceeds through design and construction, and subsequently continues for the life of the facility (through the occupancy and operations phase). Emphasis is placed upon documentation of the owner's performance criteria at the inception of the project and proper transfer of this information from one party to the next throughout the life of the project.

It is important to note that while the process interacts within the design and construction process to increase quality, it does not interfere with the competency, authority, or responsibility of licensed professionals, nor upon the obligations between owners, designers, or contractors contained in contract forms or project-specific contracts.

**1.1.1 Benefits.** Potential benefits of the Commissioning Process include:

- Reduced energy consumption and operating costs
- User acceptance and satisfaction
- Enhanced marketability and value of commercial property
- Full accountability by project participants for the quality of their work (and reduced risk exposure across the project team)
- Verification that a building and its systems generally perform as intended

These benefits can apply to existing as well as new buildings. In existing buildings, commissioning may correct unaddressed design and installation errors while calibrating the building to address the inevitable fact of building systems drifting out of alignment with the design intent and owner's operational needs over time. While engaging the Commissioning Process may produce significant benefits for a building and its owner and occupants, avoiding commissioning, or implementing commissioning incorrectly, may present significant risks that performance problems will go unaddressed.

Besides the obvious overriding benefit of owners being able to "get what they pay for," the economic benefits of correcting energy-related problems alone can produce satisfactory owner return for investing in commissioning. A study conducted by the California Energy Commission involving new and existing commercial buildings found that commissioning produced 13% median whole-building energy savings in new buildings, at a median cost of \$1.16/sq.ft., or 0.4% of the total construction cost, and 16% energy savings in existing buildings, at a median cost of \$0.30/sq.ft. Calculated payback projections were 4.2 and 1.1 years, respectively.<sup>2</sup>

**1.1.2 Commissioning and Lighting Design.** Lighting is the most visible area of electrical system design and affects all users. As a result, commissioning can make a significant difference between acceptance or rejection of more advanced lighting strategies, such as automatic lighting controls or newer energy-efficient lighting technologies.